



John Wallis Academy

Client

John Wallis Academy

Value

£4,600,000

Services

Quantity Surveying & Cost Management

Project Management

Contract Administration / Employer's Agent

Principal Designer

Sectors

Education

A new build two form entry primary school including provision for up to a hundred nursery places with extensive external works at the John Wallis Academy in Ashford, Kent.

The project creates an improved learning environment for the primary pupils who were to be relocated to the new building in the grounds of the secondary school site, adjacent to the existing academy buildings. Working on an occupied site with minimal disruption to the school was an important factor to manage.

In-keeping with the existing school campus, the external elevations comprise a buff facing brick with a white render finish applied to some first-floor elevations. The nursery elevation features cedar cladding to create a warmer feel for the younger children.

To shorten the construction period the internal leaf of the external wall was constructed utilising a metsec steel framing system tied to the building's main steel frame. Openings are fitted with aluminium casement windows and doors.



Internally the walls are plastered and finished with emulsion, generally floors are carpeted with vinyl used in wet areas and wood in the hall.

External works include a new car park, access pathways and external play and landscape scheme.

Woodley Coles provided Project Management, pre and post contract Quantity Surveying, Contract Administration and Principal Designer services for the delivery of this project.

Architect

Noviun Architects

Contractor

Abbott Construction

Structural Engineer

Considine


Electrical Services

PA Grant

Mechanical Services

Grummant





WOODLEY
COLES

Kent Office
01304 806090
kent@woodleycoles.com

London Office
020 3307 8379
london@woodleycoles.com



Cambridgeshire Office
01223 236663
cambridge@woodleycoles.com